## **NDTitans in action**



## Case 8.4 Joints testing for injection quality with DOCter impact-echo



DOCter test signals from joint testing in a 5-story building where full injection of all the joints was specified. Many joints had very bad injection. Cores, as shown, were extracted for documentation.